

SAMPLE PROJECT · EVERYTHING HERE IS MADE UP

Lakeview Medical Office Building.

Why this exists. Use this fictional project to run the live demo, so no member's real job is ever on the screen. The documents are realistic but invented. Everyone works from the same packet, on paper and on screen.

GENERAL CONTRACTOR Cascade Ridge Construction	PROJECT Lakeview Medical Office	LOCATION Bellingham, WA
TYPE 2-story MOB, 28,000 sf	DELIVERY CM at Risk, GMP	ARCHITECT / EOR Meridian / Tinsley

SUBMITTAL LOG · FOR CONTEXT

NO.	SPEC SECTION	ITEM	STATUS
03-01	03 30 00	Concrete mix design	Under review
03-02	03 20 00	Reinforcing steel shop drawings	Approved as noted
07-01	07 13 00	Sheet waterproofing	Revise and resubmit
08-01	08 71 00	Door hardware schedule	Submitted

THE DOCUMENTS · THIS IS WHAT THE AI READS

Three issues you can draft live.

ISSUE 1 · THE WARM-UP: A SPEC AND A DRAWING DISAGREE

SPEC · 03 30 00 CAST-IN-PLACE CONCRETE · 2.3 CONCRETE MIXES

A. Foundations and footings: min 28-day compressive strength f'_c = **4,000 psi**.

DRAWING · S-101 GENERAL STRUCTURAL NOTES · 3. CONCRETE

a. All footings and foundation walls: f'_c = **3,000 psi** at 28 days, unless noted.

DRAFT LIVE · RFI-003

Spec calls for **4,000 psi** foundations; the structural notes call for **3,000 psi**. The pour is next week. Ask which governs, and propose the higher strength to protect the schedule.

ISSUE 2 · THE COORDINATION CLASH: THREE TRADES, ONE CORRIDOR

DRAWING · S-301 FRAMING

Beam B-12 over Corridor 1: bottom of steel at **10'-2" AFF**.

DRAWING · M-401 MECHANICAL

Main supply duct over Corridor 1: **30" x 12"**, route above ceiling.

DRAWING · A-201 ARCHITECTURAL

Corridor 1 finished ceiling: **9'-0" AFF**.

DRAFT LIVE · RFI-004

Above the **9'-0"** ceiling, the 12" duct plus insulation and hangers needs structure near **10'-8"**. Beam B-12 sits at **10'-2"**, about six inches short. The duct cannot clear the beam and hold the ceiling. Ask to raise the beam, reroute or resize the duct, or drop the ceiling locally.

ISSUE 3 · THE MISSING DETAIL: THE HARDEST TO CATCH

DRAWING · LS-101 LIFE SAFETY

Corridor 1 walls: **1-hour fire-rated**, continuous to deck.

DRAWING · M-401 MECHANICAL

30" x 12" supply duct penetrates Corridor 1 wall at grid **C-4**.

SPEC · 07 84 00 FIRESTOPPING · 1.1

Provide tested firestop systems at all rated penetrations. (No specific system named.)

DRAFT LIVE · RFI-005

A **1-hour** corridor wall is penetrated by the supply duct at **C-4**, but no fire-smoke damper or specific firestop system is shown anywhere. Ask whether a damper is required and request the exact tested firestop system. This one is dangerous precisely because nothing on the drawings points to it.

PRIOR RFI · SO THE DRAFT MATCHES THE HOUSE FORMAT

RFI-001 · DOOR 105A SWING · TO MERIDIAN ARCHITECTS · CLOSED

Question. Plan A-201 shows Door 105A swinging into the corridor. Life-safety plan LS-101 shows it swinging into the room. Please confirm the swing direction.

Suggested resolution. Swing into the room to keep the corridor clear for egress.

Cost / schedule impact. None if resolved by framing, week of the 14th.

Response. Confirmed, door swings into the room per egress. No change order required.